

Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

REPAIR AND IMPROVEMENT OF INTERNATIONAL HOUSE II
2nd POSTING
5,842,928.32
COLLEGE/UNIT/CAMPUS: MAIN CAMPUS

Bill of Quantities

Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
----------	-------------	------	----------	--------------------	----------------

- hanger every 800mm middle on center
- Use 1/4" thick x 1.20m x 2.40m fiber cement board for ceiling boards
- Installation of 1" x 2" KD cornices on all ceiling perimeter and corners
- Installation of (D-6) 700mm x 2100mm flush door with 50mm x 100mm KD door jamb (leading to balcony), lockset and hinges at the following rooms:
 - 201
 - 203
 - 204
 - 205
 - 301
 - 303
 - 306
 - 313
 - 409

3. Fourth Floor

a. Hallway

- Installation of ceiling
 - Use 25mm x 25mm x .60mm thick wall angle
 - Use 1" concrete nail for fastening wall angle at concrete
 - Use .60mm x 19mm x 50mm x .60mm thk. J-furring as ceiling joist, parallel to the longer sides of the room spaced at 40mm middle on center
 - Use 1mm x 12mm x 38mm x 1.0mm thk. C-channel as ceiling joist, parallel

- a. This work will include the following:
 - Installation of new sewer and water supply pipeline as needed
 - Waterproofing of all sewer and water supply pipeline
 - Replacement of all water supply fittings
- b. Installation of new plumbing fixtures:
 - Installation of new water closet and lavatory including bidet, toilet accessories and water supply fittings
- c. Tap to existing source

V. Electrical Works

1. Roughing-in
 - a. This work will include the following:
 - Replacement of existing lighting power supply line (re-wiring)
2. Installation of new lighting fixtures
 - a. Function Hall
 - 16 sets of 24 Watts Recessed-type LED Panel Light, daylight, for each hall
 - b. Comfort Rooms (Function Hall)
 - 4 sets of 9-11 Watts LED downlight/pinlight, daylight, for each comfort room
 - c. Bathrooms
 - 1 set of 9-11 Watts LED Downlight/Pinlight, daylight, for each bathroom
 - d. Hallway
 - 16 sets of 24 Watts Recessed-type LED Panel Light, daylight
 - e. Installation of new wiring devices
 - f. Tap to the existing source.

VI. Painting Works

1. Site Clearing and Preparation
 - a. Interior and Exterior Wall, Concrete Beams, Columns and Canopies
 - Remove all loose, scaling, flaking, and peeling off paint by wire brushing, scraping, or rough sanding.
 -

foreign matter. Hammer all nails deep enough to apply putty. Sand rough wood until smooth and then dust off before painting.

d. Roofing